



GREAT DIVIDE - CAN LINE (12 oz @ 350 cpm: May 20, 2014

ITEM	MANUFACTURER	QTY	DESCRIPTION
EQUIPMENT, DRY AREA			
1	Busse	1	High Level Depalletizer - W Series
	Busse Option	1	Local Motor Disconnect
EQUIPMENT, WET AREA			
2	Videojet	1	Ink Jet Coder for Cans - 1620
3	A&E	1	Ionized Air Can Rinser - AV-C750
4	KHS	1	DVD 30 Can Filler & FSM
	Filler Option	1	Continuous power supply of 24 V DC (UV)
5	Ferrum	1	Can Seamer F5
	Ferrum Option	1	W/P/Foam Cleaning system-can seamer
	Ferrum Option	1	Cleaning of infeed table for table length 3000mm
	Ferrum Option	1	Surcharge drive motor 7.5kW IEC Motor IE3
	Ferrum Option	1	Air Condition unit for Terminal box for ambient temp
	Ferrum Option	1	Ball Valve (lockable) for hot water entrance
	Ferrum Option	1	Ball Valve (lockable) for CO2 entrance
	Ferrum Option	1	Ball Valve (lockable) for foam entrance
	Ferrum Option	1	Hydraulic pressure gauge
	Ferrum Option	1	Flushing Device
6	Jet Air	1	Lid Dryer w/ shield
	Jet Air Options	1	RLX Air Knife
7	Heuft	1	Basic Fill Height Inspector w/ mono rejector
EQUIPMENT, PACKER AREA			
8	Speecon	1	Laning System & manual loading station
9	GPI	1	Can Multipacker - QF200
10	Videojet	1	Ink Jet Coder for Packs - 3020
11	Hi-Cone	1	Can Multipacker - 5302
12	Intralox	1	Laner
	Intralox Option	1	Stainless Steel frames
13	KHS	1	Tray Packer TP-50
	TP Option	1	Lincoln Fully Automatic Lubrication System
14	Mettler Toledo	1	Checkweigher - CS3600 XE
15	Videojet	1	Ink Jet Coder for Trays - 2350
16	TopTier	1	Palletizer / Stretchwraper - DS
17	OEM	5	Scissors Lift
18	KHS	1	Strap Chopper
19	KHS	1	Platforms
CONVEYOR			
20	Alternative	1	Can Conveyor BTR
21	Alternative	1	Variety Pack Conveyor
22	Alternative	1	Electrical Panel ELS/BTR
23	Alternative	1	Pack Conveyor GTR
24	Alternative	1	Electrical Panel ELS/GTR
	Conveyor Option		SST MCP for conveying system
	Conveyor Option		SST conveyor leg pads
25	Alternative	1	Pack conveyor for 24pk
26	Loehrke	1	Lubrication System
MISCELLANEOUS			
27	KHS	1	Freight
SERVICES			
28	KHS	1	Engineering, Mechanical and Electrical
29	KHS	1	Project/Construction Management
30	KHS	1	Installation
31	KHS	1	Commissioning and Ramp Up
32	KHS	1	Training

ASSUMPTIONS / NOTES

GPI WrapAround Multipacks
12 oz - 12's, 24's*
*optional pack conveyors

Hi-Conve Multipacks
12 oz - 6's
16 oz - 4's

Trays
12 oz - Four 6's in 4 x 6 Tray
12 oz - Two 12's in 4 x 6 Tray
16 oz - Six 4's in 4 x 6 Tray

Installation

- customer provided main distribution panel
- hose stations, safety showers, bollards in customer's scope
- customer utilities (air, beer, CO2, etc....) located in overhead rack as indicated in plant drawing provided